सत्यमेव जयते

**Government Of West Bengal**
**Office Of The Divisional Fire Officer,Purba Medinipur**
**West Bengal Fire & Emergency Services**
**Dharinda, P.O.:- Tamluk, Purba Medinipur, Pin:- 721636**

Memo no.:WBFES/HOW/700/15

Date: 18-03-2024

**From:**
**Divisional Fire Officer,Purba Medinipur**
**West Bengal Fire & Emergency Services**

**To: DHYANESWAR SUBODH COLLEGE**
**VILL-GOGRAS COURT TALUK PO-RAGHUNATHBARI PS-PANSKURA DIST-PURBA MEDINIPUR PIN-721634**

**Sub: Renewal of Fire Safety Certificate for existing construction G+II Storied Building under group of Educational Building in the name & style of "DHYANESWAR SUBODH COLLEGE" at Premises Village- Gogras Court Taluk PO- Raghunathbari PS- Panskura District- Purba Medinipur Pin-721634.**

This is in reference to your application no. 0125191241400020 dated 19-02-2024 regarding the Renewal of Fire Safety Certificate for existing construction G+II Storied Building under group of Educational Building in the name & style of "DHYANESWAR SUBODH COLLEGE" at Premises Village- Gogras Court Taluk PO- Raghunathbari PS- Panskura District- Purba Medinipur Pin-721634.

The performance of the Fire Fighting System as incorporated in the buildings were tested at random and found satisfactorily working condition. In view of the above this office is releasing the Renewal of Fire Safety Certificate for occupancy of the aforesaid building.

However to up-keep the Fire Safety Measure of the aforesaid building the following safety measures need to be incorporated / maintained.

**Recommendation:**
On conditional Renewal of Fire safety Certificate Allow, subject to comply the following condition with in Three months from issuing of this Certificate and intimate to this end with photo proof for regularization of the same.
Conditions,-
i) As standby pump another same capacities Pump will be installed, all pumps will intrigued with auto driven facilities.
ii) Sprinkler will be installed at library and laboratory as per relating ISI specification.
iii) Under Ground reservoir not as per Recommendation, require to provide at least 20000 ltrs. capacity U/G reservoir.
iv) If any other establishment is exist, must be applied for RFSR with in THREE months.
v) also require to provide another stair case at opposite side of second Stair for over come the dead end.

Memo No.:WBFES/HOW/700/15

The authenticity of this document can be verified by accessing the URL: edistrict.wb.gov.in and then clicking on the 'Verification of Digitally Signed Document' link and keying in the Unique Number : 0125191241400020.

except the above the other conditions are as follows ;-

1)Driveway must be free of any type of obstruction for easy movement of Fire Appliances. No Parking will be allowed on the Driveway.

2)One standby pump shall be installed shall be connected with auto start facility.

3)Over head water reservoir shall be extended another 5000 liters.

4)LPG Gas bank shall be made outside the Kitchen and kitchen shall be protected with CO2 extinguisher.

5)Exit ways shall be marked properly and all exit ways shall remain open during working hours.

6)The Interior finish decoration of building shall be made with low flame spread material conforming to the IS Specification.

7)To eliminate risk of Fire Hazards, Good House Keeping both for insides and outside of the building shall be strictly maintained.

8)Electrical wiring of the whole building shall have to be carefully checked for any where any tear in them, particularly lines having false ceiling and ducts,

9)The notice of Fire Fighting and Evacuation from the building shall be prepared and displayed at all venerable of the building.

10)The employees and security staff shall be conversant with installed Fire Fighting equipment's of the building and to operate in the event of Fire and Testing.

11)Mock Fire Practice and evacuation drill shall be performed periodically with Participants of all the occupants of the building.

12)Meter room shall be protected with Co2 Fire Extinguisher conforming IS specification,

13)First-Aid Fire Fighting system shall be provided as per I.S specification.

14)Arrangement shall have to be made for regular checking, testing and maintenance of all the Fire Fighting installation in the building to keep them in perfectly good working condition at all the times.

15)Periodical flashing of water in the Hose Reel Hose line shall be made to maintain the efficiency working performance of above mention system.

16)If required the old lines shall have to be replace with new lines cables shall always be laid in M.S. conduct pipes continuously bounded to the earth,

17)The Fire Safety audit to be conducted a regular interval and to be recorded in the Fire Prevention maintenance register.

Memo No.:WBFES/HQW/700/15

The authenticity of this document can be verified by accessing the URL: edistrict.wb.gov.in and then clicking on the 'Verification of Digitally Signed Document' link and keying in the Unique Number : 0125191241400020.

18)Revised Fire Safety Recommendation shall be applied for any addition & alternation made in the structure.

19)This Renewal Fire Safety Certificate is valid for three years and has to be renewed in every three years from the date of issue of this letter Vide Notification No.- 629_L dated 17.04.2018 and Memo No.- WBFES/604(200)/2919 dated 01.02.2019.

20)The Renewal Fire Safety Certificate is to be obtained from the Divisional Fire Officer, Purba Medinipur Division, West Bengal Fire and Emergency Services performance of all the life and Fire Safety arrangements and installations of the building.

Signature valid

Digitally Signed.
Name: Bam Kumar Chowdhury
Date: 18-Mar-2024 16:25:14
Reason: Approved
Location: West Bengal

Divisional Fire Officer,Purba Medinipur
West Bengal Fire & Emergency Services

Memo No.:WBFES/HOW/760/19

The authenticity of this document can be verified by accessing the URL: edistrict.wb.gov.in and then clicking on the 'Verification of Digitally Signed Document' link and keying in the Unique Number : 0125191241400020.